



NOTES:

1. CONTRACTOR SHALL STRIKE CONTROL JOINTS EVERY 5'-0" AND PLACE EXPANSION JOINTS EVERY 20'-0"
2. CONTRACTOR TO INSTALL 1/2" PREFORMED EXPANSION JOINT MATERIAL AT ALL EXPANSION JOINTS AND WHERE SIDEWALK ABUTS CONCRETE CURB, FOUNDATIONS, APRONS, OR OTHER CONCRETE STRUCTURES.
3. USE APPROVED SEALANT OVER ALL SIDEWALK EXPANSION JOINTS.

CONCRETE SIDEWALK  
NTS

	The Town of Mount Airy, Maryland  APPROVED	CONCRETE SIDEWALK	By: MDH	Date 12/20/21
				Standard Detail No. R-12